

Larkspur DC-04 / approval drawing

FICTIONAL REPLAY - not a design certification or commercial offer

Document role: drawing

Revision: B

52-M1 | rated_voltage_v: 480 V

52-M1 | frequency_hz: 60 Hz

52-M1 | phases: 3

52-M1 | wires: 4

52-M1 | main_bus_a: 3200 A

52-M1 | neutral_bus_percent: 100%

52-M1 | short_circuit_ka: 65 kA

52-M1 | short_time_ka: 65 kA

52-M1 | short_time_duration_s: 0.5 s

52-M1 | main_breaker_frame_a: 3200 A

52-M1 | main_breaker_trip_a: 2500 A

52-M1 | main_breaker_poles: 3

52-M1 | main_breaker_interrupting_ka: 100 kA

52-M1 | feeder_breaker_frame_a: 800 A

52-M1 | feeder_breaker_trip_a: 600 A

52-M1 | enclosure_type: NEMA 1

52-M1 | bus_material: aluminum

52-M1 | bus_plating: silver

52-M1 | cable_entry: bottom

52-M1 | control_voltage_v: 120 V

52-M1 | metering: multifunction

52-M1 | communications_protocol: Modbus RTU

52-M1 | surge_protection: yes

52-M1 | ground_fault_protection: yes

52-M1 | arc_resistant: no

52-M1 | seismic_qualification: Project-specific review required

52-M1 | enclosure_width_mm: 2200 mm

52-M1 | enclosure_height_mm: 2200 mm

52-M1 | enclosure_depth_mm: 1000 mm

52-M1 | quantity: 1

52-M1 | manufacturer: Fictional Aster Equipment

52-M1 | catalog_number: ASTER-LV-3200-DEMO

52-M1 | nameplate_text: MSB-01 / 480 V / 65 kA

Larkspur DC-04 / approval drawing

FICTIONAL REPLAY - not a design certification or commercial offer

52-M1 | lead_time_weeks: 28 weeks