

Larkspur DC-04 / approval drawing

FICTIONAL REPLAY - not a design certification or commercial offer

Document role: drawing

Revision: C

MSB-01 | rated_voltage_v: 480 V

MSB-01 | frequency_hz: 60 Hz

MSB-01 | phases: 3

MSB-01 | wires: 4

MSB-01 | main_bus_a: 3200 A

MSB-01 | neutral_bus_percent: 100%

MSB-01 | short_circuit_ka: 65 kA

MSB-01 | short_time_ka: 65 kA

MSB-01 | short_time_duration_s: 0.5 s

MSB-01 | main_breaker_frame_a: 3200 A

MSB-01 | main_breaker_trip_a: 3000 A

MSB-01 | main_breaker_poles: 3

MSB-01 | main_breaker_interrupting_ka: 100 kA

MSB-01 | feeder_breaker_frame_a: 800 A

MSB-01 | feeder_breaker_trip_a: 600 A

MSB-01 | enclosure_type: NEMA 3R

MSB-01 | bus_material: aluminum

MSB-01 | bus_plating: silver

MSB-01 | cable_entry: top

MSB-01 | control_voltage_v: 120 V

MSB-01 | metering: multifunction

MSB-01 | communications_protocol: Modbus TCP

MSB-01 | surge_protection: yes

MSB-01 | ground_fault_protection: yes

MSB-01 | arc_resistant: no

MSB-01 | seismic_qualification: Project-specific review required

MSB-01 | enclosure_width_mm: 2400 mm

MSB-01 | enclosure_height_mm: 2200 mm

MSB-01 | enclosure_depth_mm: 1000 mm

MSB-01 | quantity: 1

MSB-01 | manufacturer: Fictional Aster Equipment

MSB-01 | catalog_number: ASTER-LV-3200-DEMO

MSB-01 | nameplate_text: MSB-01 / 480 V / 85 kA

Larkspur DC-04 / approval drawing

FICTIONAL REPLAY - not a design certification or commercial offer

MSB-01 | lead_time_weeks: 28 weeks

Drafter response to comment 7: Fixed in Rev C.